BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the work: Emergency works in ward no. 08, kodigehalli

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	1346.55	Removing and resetting of footpath slab	sqm	208.82	
2	16.89	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. - reinforced cement concrete grade M20 and above	cum	1684.34	
3	25.70	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. - rubble stone masonry in cement mortar	cum	372.06	
4	819.47	KSRRB 300-2 : Earth work excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3	Cum	137.80	
5	11.01	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	5408.12	
6	10.28	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1: 6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. - Available stones	Cum	3287.73	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	33.78	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1: 6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. - New stones	Cum	4871.76	
8	97.92	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	150.52	
9	11.61	Providing and laying in position plain cement concrete of mix 1:2:4 with cement at 240 kg, with 20mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates at 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted for coping including cost of all materials, labour, HOM of machinery, curing, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Cum	5599.98	
10	73.44	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. - 250 mm thick	Sqm	5418.00	
11	149.61	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. - 100 mm thick	Sqm	2337.00	
12	225.00	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications	Cum	2001.28	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
13	600.00	Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications	~~No.~~	365.70	
14	600.00	Supply of drinking water through water tankers of capacity 5000 litres, hiring of water tankers, hire charghes of tractor 40 HP including operator and fuel, procurement of water, engaging heavy mazdoor with all leads and lifts as directed by the Engineer in charge of the work	No.	629.24	
15	9.00	RCC pjipes NP2 900 mm dia including collars as directed including cost of all materials, labour, transportation, all leads and lifts etc	Rm	2444.92	
16	2.58	20mm jelly around dug well	Cum	1091.43	
17	4.00	Reinforced Cement concrete cover slab of 1.20m dia as directed including cost of all materials, labour, transportation, all leads and lifts etcconcrete cover slab	No.	2500.00	
18	696.55	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	Cum	106.00	

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed
2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.